



# Initial Thermal Performance of a Tailings Retaining Frozen Foundation Dam, Nunavut, Canada

Christopher Stevens, John Kurylo, and Peter Luedke

Canadian Permafrost Association – Annual General Meeting  
November 16, 2020


# Outline

- Dams with frozen components
- Hope Bay tailings impoundment area (TIA)
- South Dam design & construction
- Foundation conditions
- Initial thermal performance (just a glimpse)



# Dams with Frozen Components


**Frozen Foundation Dam  
(Tailings Soilds Retention)**



**LEGEND**

- Upper GCL Liner
- Water
- Tailings
- Water saturated material
- Bedding Material
- Transition Material
- Run of Quarry Backfill

**Frozen Core Dam  
(Water Retention)**



# Hope Bay


## Hope Bay

TMAC Resources (100% interest)  
Gold mine  
Nunavut, Canada  
Continuous zone of permafrost




# Tailings Impoundment Area

Historical Airphoto  
Prior to Development



Recent Airphoto  
August 2019




# South Dam

- Design life 25 years
- Tailings retaining structure
- Stability and containment relies on permafrost
- Phase 1 – constructed in winter of 2018
- Phase 2 – downstream raise in 2023


Upstream

Downstream






Dam alignment prior to construction



Cross-Section along key trench

# Stratigraphy

- Glaciomarine silty clay and clayey silt, underlain by sand and gravel till
- Ground ice increases in upper 3 m, with massive ice
- New FPD of  $-0.2^{\circ}\text{C}$  (max.  $-0.6^{\circ}\text{C}$ ,  $n=110$ )







**Interbedded silt and clay**



**Segregated ice lenses**



Reticulate ice



Ice Wedges

# Design Considerations

- Foundation conditions
  - Thick permafrost soils
  - Massive ground ice & ice-rich soil
  - Cold permafrost  $-7.6^{\circ}\text{C}$
  - Porewater salinity / depressed freezing point
  - Creep susceptible
  - Low strength soils when thawed
  - Basalt bedrock
- Climate change
- Tailings deposition plan
- Lack of natural borrow materials
- Timing of construction
- Remote location of site

*Thermal regime of the dam is largely controlled by atmosphere-to-surface heat exchange, thermal and physical conditions along the upstream face of the dam, and heat transfer through the fill material & foundation*






**Foreground: Drilling of blast holes**  
**Background: Key trench excavation**




**Near complete section of key trench**




**Deployment of liner on upstream slope of key trench**



**Backfilling of key trench above liner**



**Deployment of liner on upstream slope of above ground fill**



**Deployed liner on upstream slope of above ground fill**



2018



2019

*Tailings beach development from the dam ceases in the winter to promote heat loss and to limit ice entrainment immediately upstream of the dam*



**Tailings discharge line along crest of dam**





**Tailings discharge from spigot along upstream face of dam**



# Ground Temperature Monitoring

- BeadedStream ground temperature cables and loggers
- Six sections along alignment monitored
- Each section typically 5 cables
- Data transmitted every 12 hours via iridium satellite




# Upstream and Downstream Toe

- Active layer thickness < 1 m
  - Influenced by thickness of overlying rock fill
  - Season thaw has not taken place in the foundation beneath the tailings beach


Station	GTC ID	Location	Thaw Depth, 0°C Isotherm (m)
0+155	SD-VTS-155-US	UST	-
	SD-VTS-155-DS	DST	0.0
0+240	SD-VTS-240-US	UST	0.9
	SD-VTS-240-DS	DST	0.6
0+365	SD-VTS-365-US	UST	0.0
	SD-VTS-365-DS	DST	0.1
0+460	SD-VTS-460-US	UST	0.9
	SD-VTS-460-DS	DST	0.9

Active layer < 1 m (0°C isotherm)


Section 0+65




Section 1+55




Section 2+40




Section 3+65




Section 4+60




Section 5+10




# Section 4+60




## Upstream



## Key Trench




## Downstream




Active layer ↓


## Section 3+65



## Upstream



## Downstream




# Key Trench

- General reduction in maximum annual key trench temperature compared to 2018
- GCL remains keyed-in to frozen permafrost (critical compliance point)
- Key trench temperatures are within the expected range of model predictions

Station	GTC ID	Maximum Ground Temperature (°C)		
		2018	2019	2020
0+065	SD-VTS-065-KTC	-	-4.7	-6.0
0+155	SD-VTS-155-KTC	-	-5.5	-6.2
0+240	SD-VTS-240-KTC	-7.2	-7.3	-7.6
0+365*	SD-VTS-365-KTC	-6.9	-	-
0+460	SD-VTS-460-KTC	-3.9	-4.7	-5.9
0+510	SD-VTS-510-KTC	-3.2	-4.8	-5.8

2020 ground temperature as of Oct. 28<sup>th</sup>



# Summary

- South Dam was designed as a frozen foundation tailings retaining structure
  - Construction over the winter 2018
- Continuous development of an upstream tailings beach
  - Promote winter heat loss
  - Limit ice entrainment immediately upstream dam
  - Reduce potential for seepage
- Ground temperatures indicate:
  - Dam is thermal performing and within the expected range of model predictions
  - Key trench shows continued cooling and liner tie-in remains frozen (Approx.  $-5.5^{\circ}\text{C}$  to  $-7.5^{\circ}\text{C}$ )
  - Tailings beach has begun to freezeback, largely attributed to proper tailings management
- Thermal monitoring is only one type of operational monitoring and surveillance of the TIA
  - Surface and deep settlement monuments, UAV and satellite imagery, daily and weekly site inspections, etc.

